



**THE KOLLAM DISTRICT
CO-OPERATIVE BANK LTD**

Head Office: Kollam

Head | Chinnakkada, P.B. No. 130
Office | Kollam-691 001, Kerala, India
Phone | 0474-2742301 to 2742305
Fax | 0474-2748060
E-mail | email@kollamdcdb.com
Website | www.kollamdcdb.com

No.Est/2018/

06/10/2018

ദർഘാസ് പരസ്യം

ബാങ്കിന്റെ ചക്കുവള്ളി ശാഖയുടെ മുൻവശം ഏകദേശം 1023 ച.അടി (95m²) സ്ഥലത്ത് കോൺക്രീറ്റ് ഇന്റർ ലോക്ക് കട്ടകൾ പാകുന്നതിലേയ്ക്കായി മൽസര സ്വഭാവമുള്ള ദർഘാസുകൾ ക്ഷണിച്ചുകൊള്ളുന്നു. ദർഘാസുകൾ 15.10.2018 വൈകുന്നേരം 4 മണി വരെ സ്വീകരിക്കുന്നതും അന്നേ ദിവസം 4.30 മണിക്ക് തുറക്കുന്നതുമായിരിക്കും..

കൂടുതൽ വിവരങ്ങൾ ബാങ്കിന്റെ വെബ്സൈറ്റിൽ നിന്നോ ഹെഡ്ഓഫീസിൽ നിന്നോ ലഭ്യമാകുന്നതാണ്.

(ഒപ്പ്)
ജനറൽ മാനേജർ

THE KOLLAM DISTRICT CO-OPERATIVE BANK LTD

HEAD OFFICE : KOLLAM

Name of work: Laying interlocking paver block in the front yard of
Chakkuvely Branch of the Kollam District Co-operative Bank
Schedule of Work

Sl. No	Description	Quantity	Unit	Rate Rs.	Amount Rs.
1	Earth work excavation in ordinary soil for cutting ramp, removing coconut roots, and spreading the soil in the yard with in a lead upto to 50 m and lift upto 1.5m	2m ³	cum		
2	Cutting available earth, spreading in the yard and consolidating at optimum water content with in a lead upto 50m & lift upto 1.5m	5m ³	cum		
3	Providing and laying 60mm thick factory made cement concrete interlocking paver block of M.30 grade made by block making machine with strong vibratory compaction of approved size, design and shape and in required pattern over and including 50mm compacted bed of coarse M.sand, filling the joints with fine sand etc complete.	95m ²	sqm		
4	Providing and laying in position cement concrete 1:4:8 using 40mm nominal size broken stone in the yard, levelling, compacting etc complete including curing.	0.8m ³	Cum		
5	Do using 20mm nominal size broken stone do.	0.4m ³	cum		
6	15mm thick cement plaster of mix 1:3, finished with thread lining including curing.	10m ²	Sq.m		
	(Rupees	only)	GRAND TOTAL		

Name and Signature